## FINANCIAL BID (Schedule of Quantities)

## NIT No. - CURAJ/R/F.153/2024/3466 dated 05.01.2023

## Name of Work: Replacement of Existing LED Signage Board with New LED Signage Board of 4'x72' sq. ft. Size at Administrative Building, Central University of Rajasthan.

PART-1: Dismantling and Shifting cum Re-installation of existing LED Signage Board of 3.5'x26' sq. ft. from Administration Building, CURaj.							
Sr. No.	Description of Item	T/Qty	Unit	Rate incl. GST	Amount (in Rs.)		
1	Dismantling of existing LED Signage Board of 3.5'x26' sq. ft. with associated accessories from the terrace of the Administration Building and Shifting cum Re- installation on new location within the campus i/c connections, testing & commissioning and making the wall same as earlier complete etc. as reqd on site as per standard practice and directions of EIC.	1	job				
	Total Amount incl. GST (Item No-01) = A						
		ew LED S	Signage	Board of 4'x7	72' sq. ft. at		
2	Design, Supply, Installation, Testing and Commissioning of CNC Cut Letters /Logo /Alphabets with UV Printed wherever required using 04 mm imported acrylic sheet in the desired color, font, language and as per site requirement and the letters may be raised or flushed to the box as per directions of the EIC. Make: A-Cast / Astari / Lexan.	500	Sq.ft.				
3	Making the base box with ACP sheet 4 mm thick top and base of 1mm GI sheet fixed over MS frame including Providing & Fixing CNC Cut & Bend Aluminum Composite Panel Sheet of 04 mm thick in the desired shape, size & color as per site requirement and standard practice with minimum 05 years on site OEM Warranty. Size of box will be measured for payment purpose. Make: Aludecor /Alex /Alstrong.	350	Sq.Ft.				
4	Providing, Fixing, wiring & Testing & Commissioning of 1.0 to 1.5 watt, 12 V, LED Modules of Red/White/Blue color for backlighting inside the letters/logos/Alphabets etc. as per std practice and directions of EIC with minimum 05 years on site OEM Warranty. Make: OSRAM/GE/BAJAJ/Philips.	3000	each				
5	SITC of 300 watt rated water proof LED Controller including connections etc. as reqd on site and directions of EIC with minimum 05 years on site OEM Warranty. Make: OSRAM/PHILIPS/UNION.	20	each				

6	P&F of steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. (M.S. Frame 50 mm x 50 mm x 4 mm hollow tubes) complete with all vertical and horizontal supports including required welding, bolt, nut, washer etc. for the entire signage & back supports of 50 mm x 50 mm x 6 mm Iron Angles complete with two coat of primer & two coat of enamel paint as per std practice and directions of EIC.	1300	Kg.	
7	Supplying, laying, testing & commissioning of 03 core 4 Sq. mm, armored, PVC Insulated, XLPE, aluminum conductor cable complete with glands, lugs etc. as reqd on site as per std practice and directions of EIC. Make: Polycab/RR Kabel/KEI/Havells.	100	RMT	
8	Supply, fixing, testing & commissioning of suitable capacity distribution box, along with MCBs, contactor, connectors, timer etc. as required on site as per std practice and directions of EIC. Make: L&T/ Schneider/ABB/Legrand/C&S.	2	each	
	Total Amount incl. GST (Item No-02 to 08) = B			
	Gross Amount incl. GST (Item No-01 to 08) = A+B = C			

## NOTE:

- 1) The bidder should quote the rates after visiting the site.
- 2) The above work includes five (05) years on site comprehensive maintenance from the date of commissioning and handing over the site with requisite documentation.
- *3)* The successful bidder must have to submit the LED Signage Board mounting structure safety certificate for its safe life of at least 05 years.
- 4) The quoted rates shall be inclusive of all taxes, labour, tools & plants and overhead charges etc. Nothing shall be paid extra in this regard.

Seal & Signature of Bidder:

Name of Firm: