




राजस्थान केन्द्रीय विश्वविद्यालय
Central University of Rajasthan
 NH-8, Bandarsindri, Kishangarh-305817, Ajmer(Raj.)



NIT No. CURAJ/R/F151/2023/2174

Date:21.09.2023

Financial Bid

Name of Work: Repair & Maintenance work for Pond Boundray Wall at Central University of Rajasthan, Bandarsindri, Dist. Ajmer, Rajasthan.

NIT No.

Date:

S. N	Description	Qty	Unit	Rate	Amount
1	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with.				
1.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	196	Cum	6653.5	1304076.00
2	20 mm cement plaster of mix .				
2.1	1:4 (1 cement: 4 coarse sand)	332.5	Smq	421.40	140115.50
3	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge :				
3.1	In cement mortar	98	Cum	2027.1	198655.80
4.0	Removing mortar from and cleaning stones and concrete articles (net quantity of stacks of cleaned materials will be measured):				
4.1	In cement mortar	58.8	cum	568.15	33407.22
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
5.1	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	36.75	cum	8364.20	307384.40
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				

6.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	58.06	Kg	89.65	5205.07
7	Centering and shuttering including strutting, propping etc. and removal of form for.				
7.1	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	52.50	sqm	608.35	31938.38
7.2	Walls (any thickness) including attached pilasters, buttersesses, plinth and string courses etc.	280	Sqm	699.55	195874.00
	Total			Rs.	2216657.00
	Add Ajmer cost Index @ 1.08%			Rs.	23939.89
	Sub Total			Rs.	2240596.00
	Add GST @ 6.33%			Rs.	141829.80
	Sub Total			Rs.	2382426.00
8	Old material of Stone for masonry work will be credited to the contractor.	60	Cum	-1100	-66000.00
	G.Total			Rs.	2316426
	Amount quoted in percentage, over/above/at par				

*Note: The Goods and Service Tax, Turnover Tax, Excise Duty, Work Contract Tax, or any other Tax as applicable shall be paid by the contractor himself. **The bidder shall quote his rates considering all such Taxes.***

Seal & Signature of Bidder
Date: