



राजस्थान केन्द्रीय विश्वविद्यालय
Central University of Rajasthan
H-8, Bandarsindri, Kishangarh-305817, Ajmer(Raj.)

Financial Bid

Name of Work: Maintenance of Overhead signages at Central University of Rajasthan.

NIT No. CURAJ/R/F.141/2022/2566

Date:11.10.2022

S. N	Description	Qty	Unit	Rate	Amount
1	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m.				
1.1	All kinds of soil	40	Each		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level				
2.1	1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	7.29	Cum		
3	Centering and shuttering including strutting, propping etc. and removal of form for :				
3.1	Foundations, footings, bases of columns, etc. for mass concrete	64.8	Sqm		
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	500	kg		
5	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
5.1	Hot finished welded type tubes	300	Kg		
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
6.1	Two or more coats on new work	50	Sqm		
7	Manufacturing, supplying and fixing retro reflective overhead signage boards made up				

	of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-incharge.(Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment).				
7.1	Overhead informatory road signage	62.00	Sqm		
	Total Amount inclusive GST & others			Rs.	

*Note: The Goods and Service Tax, Turnover Tax, Excise Duty, Work Contract Tax, Or any other Tax as applicable shall be paid by the contractor himself. **The contractor shall quote his rates considering all such Taxes.***

Bidder

Seal & Signature of

Date: