

राजस्थान केन्द्रीय विश्वविद्यालय

Central University of Rajasthan H-8, Bandarsindri, Kishangarh-305817, Ajmer(Raj.)

Financial Bid

Name of Work: Internal identical signages boards in the Non-residential and Residential Buildings at Central University of Rajasthan.

NIT No. CURAJ/R/F.141/2022/2989

Date: 14.11.2022

S. N	Description	Qty	Unit	Rate	Amount
	Providing and fixing of internal Signage at the				
	various locations in the University				
	Internal Signage: Room Number Plates on				
	golden ACP Sheet base & Black colour reflective				
1	Vinyle cutting letters fixing with mirror screw etc.				
-	complete.				
	Note: Rate shall include all transporation, labour				
	charges, finishing all complete.		_		
	All materials to be used needs prior approval of		Sq.		
	Engineer - in -charge.	11016	inch		
	Providing and fixing of bilingual internal Signage at				
	the various locations in the University				
	Internal Signage: Name Plates on golden ACP				
	Sheet base & Black colour reflective Vinyle cutting				
	letters fixing with mirror screws etc. complete as				
	per the directions of the Engineer-in-charge				
	Note: Rate shall include all transporation, labour				
	charges, finishing all complete.		a .		
2	All materials to be used needs prior approval of	24600	Sq.in		
2	Engineer - in -charge.	24600	ch		
	Providing and fixing building floor plan on ACP				
	sheet Base & Viny print laminated duly fitted on				
	0.75" x0.75" Stainless Steel make studs, as per				
	directions of the Engineer in-charge. Note: Rate shall include all transporation, GST,				
	labour charges, finishing all complete.				
	All materials to be used needs prior approval of		Sq.in		
3	Engineer - in -charge.	57600	ch		
	Providing and fixing Department Names floor wise	27000			
	on ACP sheet Base & Vinyl print laminated duly				
	fitted on 0.75" x .075 " Stainless Steel make studs ,				
	as per directions of the Engineer in-charge.				
	Note: Rate shall include all transporation, GST,				
	labour charges, finishing all complete.				
	All materials to be used needs prior approval of		Sq.in		
4	Engineer - in -charge.	66816	ch		

	Providing and fixing University's vision and				
	Mission on 4mm thick black acraylic sheet with				
	Golden Vinyle Cutting Letters duly fitted on 0.75" x				
	.075 " Stainless Steel make studs , as per directions				
	of the Engineer in-charge.				
	Note: Rate shall include all transporation, GST,				
	labour charges, finishing all complete.				
	All materials to be used needs prior approval of		Sq.in		
5	Engineer - in -charge.	65664	ch		
	Manufacturing, supplying and fixing retro				
	reflective overhead signage boards made up of 2				
	mm thick aluminium sheet, face to be fully covered				
	with high intensity and encapsulated lens type heat				
	activated retro reflective sheeting conforming to				
	type - III of ASTM-D-4956-01 as approved by				
	Engineer-in-charge, letters, borders etc. as per IRC :				
	67-2001 in silver white with blue colour back				
	ground and with high intensity grade, pasted on				
	substrate by pressure sensitive adhesive backing				
	which shall be activated by applying pressure				
	conforming to class II of ASTM-D-4956-01 and				
	fixing the same to the plate of structural frame work				
	by means of suitable sized aluminium alloys, rivets				
	or bolts & nuts @ 300 mm centre to centre all along				
	the periphery as well as in two vertical rows along				
	with theft resistant measures, including the cost of				
	painting with two or more coats of epoxy paint in				
	grey colour on the back side of aluminium sheet				
	including appropriate priming coat. The rate				
	includes the cost of rounding off the corners, fixing				
	and erecting the same in position all complete as per				
	drawings, specification and direction of the				
	engineer-incharge.(Structural frame work including				
	M.S. plate to be provided separately. Rectangular				
	area of the sheet only shall be measured for				
6	payment).				
		104.00	G		
6.1	Overhead informatory road signage	134.00	Sqm		
	Structural steel work riveted, bolted or welded in				
	built up sections, trusses and framed work,				
	including cutting, hoisting, fixing in position and				
	applying a priming coat of approved steel primer all				
7	complete.	4000	kg		
	Total Amount inclusive GST & others			Rs.	

Note: The Goods and Service Tax, Turnover Tax, Excise Duty, Work Contract Tax, Or any other Tax as applicable shall be paid by the contractor himself. The contractor shall quote his rates considering all such Taxes.

Seal & Signature of Bidder Date: